



FORT DUPONT POOL LEAD WATER TEST RESULTS May 16th, 2016



Building Location	Sample Collected Date	Water Source ID	Device Type	Floor	Device Location	1st Draw - Sample ID	Final Result - 1st Draw (ug/L)	2nd Draw - Sample ID	Final Result - 2nd Draw (ug/L)	Remediation	Retest Date	Retest 1st Draw	Retest 2nd Draw
1 FORT DUPONT POOL	5/25/2016	WS- 003799	Utility	Ground Floor	Exterior door adjacent pool	WT-042916-3816- A	< 1	WT-042916-3816- B	< 1				
2 FORT DUPONT POOL	5/25/2016	WS- 003800	Fountain	Ground Floor	Exterior adjacent to pool Low	WT-042916-3817- A	< 1	WT-042916-3817- B	< 1				
3 FORT DUPONT POOL	5/25/2016	WS- 003801	Fountain	Ground Floor	Outside adjacent to pool Left High	WT-042916-3818- A	< 1	WT-042916-3818- B	< 1				
4 FORT DUPONT POOL	5/25/2016	WS- 003802	Kitchen	Ground Floor	In kitchen 1st sink Left	WT-042916-3819- A	< 1	WT-042916-3819- B	< 1				
5 FORT DUPONT POOL	5/25/2016	WS- 003803	Kitchen	1	In kitchen 2nd sink Mid	WT-042916-3820- A	< 1	WT-042916-3820- B	< 1				
6 FORT DUPONT POOL	5/25/2016	WS- 003804	Kitchen	1	In kitchen 3rd sink Right	WT-042916-3821- A	< 1	WT-042916-3821- B	< 1				
7 FORT DUPONT POOL	5/25/2016	WS- 003805	Kitchen	1	Ice machine	WT-042916-3822- A	< 1	WT-042916-3822- B	< 1				
8 FORT DUPONT POOL	5/25/2016	WS- 003806	Cooler	1	In hallway adjacent to room 110 aquatics office High	WT-042916-3823- A	< 1	WT-042916-3823- B	< 1				
9 FORT DUPONT POOL	5/25/2016	WS- 003807	Cooler	1	In hallway adjacent room 110 aquatics office	WT-042916-3824- A	< 1	WT-042916-3824- B	< 1				
10 FORT DUPONT POOL	5/25/2016	WS- 003808	Cooler	Ground Floor	In hallway adjacent room 110 aquatics office Low	WT-042916-3825- A	< 1	WT-042916-3825- B	< 1				
11 FORT DUPONT POOL	5/25/2016	WS- 003809	Cooler	1	In hallway adjacent room 100 High	WT-042916-3826- A	< 1	WT-042916-3826- B	< 1				
12 FORT DUPONT POOL	5/25/2016	WS- 003810	Cooler	1	In hallway adjacent room 100 Mid	WT-042916-3827- A	< 1	WT-042916-3827- B	< 1				
13 FORT DUPONT POOL	5/25/2016	WS- 003811	Cooler	1	In hallway adjacent to room 100 Low	WT-042916-3828- A	< 1	WT-042916-3828- B	< 1				
14 FORT DUPONT POOL	5/25/2016	WS- 003812	Classroom	1	In room 104 arts and crafts	WT-042916-3829- A	< 1	WT-042916-3829- B	< 1				
15 FORT DUPONT POOL	5/25/2016	WS- 003813	Classroom	1	In room 106 Goldens	WT-042916-3830- A	< 1	WT-042916-3830- B	< 1				
16 FORT DUPONT POOL	5/25/2016	WS- 003814	Fountain	Ground Floor	Exterior adjacent to playground Low	WT-042916-3831- A	< 1	WT-042916-3831- B	< 1				
17 FORT DUPONT POOL	5/25/2016	WS- 003815	Fountain	Ground Floor	Exterior adjacent to basketball court High	WT-042916-3832- A	3.8	WT-042916-3832- B	< 1				
18 FORT DUPONT POOL	5/25/2016	WS- 003816	Fountain	Ground Floor	Exterior adjacent to basketball court Low	WT-042916-3833- A	6.8	WT-042916-3833- B	< 1				
19 FORT DUPONT POOL	5/25/2016	WS- 003817	Fountain	Ground Floor	Exterior adjacent to the playground High	WT-042916-3834- A	< 1	WT-042916-3834- B	< 1				

Footnotes:

- A - First draw sample is collected after the plumbing system has not been used for at least 6 hours.
- B - Second draw sample is collected after a 60 second flush at that device after the first draw.