

DCAM-22-NC-IFB-0006
ADDENDUM NO. 02 - EXHIBIT A

NO.	QUESTION	ANSWER
1	While information is noted for specifications on access control and intrusion detection hardware, specifications for some items are not found on documentation. What is the make of preferred camera? Is Axis an acceptable make? We would assume that any HIKvision or Dahua OEM manufactured hardware is strictly prohibited.	Axis cameras are a part of the Approved Products List (APL) provided as Exhibit J.8.
2	What is the preferred model of camera for a. Exterior Camera: is P3265-LVE acceptable or do you have another model?	P3265-LVE is a part of the Approved Products List (APL) provided as Exhibit J.8.
3	Interior Camera: is P3265-V acceptable or do you have another model?	P3265-V is a part of the Approved Products List (APL) provided as Exhibit J.8.
4	Exterior 180/360 Degree Camera: is P3727-PLE acceptable or do you have another model?	P3727-PLE is a part of the Approved Products List (APL) provided as Exhibit J.8.
5	Interior 180/360 Degree Camera: is P3727-PLE acceptable or do you have another model?	P3727-PLE is a part of the Approved Products List (APL) provided as Exhibit J.8.
6	Milestone Headend for 32 Cameras, which is the preferred device: Husky 350R, 700R or 1000R?	Milestone Husky 700R is accepted as part of the Approved Products List (APL) provided as Exhibit J.8.
7	Assuming Cisco is the required Network IP Camera PoE Switch, is there a preferred model or should we select an appropriate model? If so, should this be a layer3 or layer4 switch? Should it have fiber uplink of 10G?	The preferred model for our Network IP Cameras is PoE Switch with Axis Switch per the Approved Products List (APL) provided as Exhibit J.8. The appropriate Switch should be layer 3 with a fiber uplink of 10G.
8	What Rackmount UPS is preferred?	Rackmount UPS preferred would be APC. Please refer to Approved Product List (APL) Exhibit J.8.
9	What UPS uptime is expected, is 30 minutes sufficient?	The expected UPS uptime is 30 minutes.
10	What exterior camera pole is required? Should this be a pole that can be tilted to work on, or a pole that would require a "cherry picker" to work on?	A Cherry Picker would be required for this action.
11	There is a listing for 1" conduit, is the column "Conduit in feet" equal to 1/2" or 3/4" conduit?	The conduit in feet should be 3/4".
12	"Trenching per foot includes conduit and backbox", is that through soil only, or does concrete also exist in the pathway? And is it correct to assume that the rule of 36" dept to get below the frostline applies?	Trenching per foot will include conduit and backbox it is through soil and concrete and also the existing pathway. The rule of 36 inches dept to get below the frostline does apply.
13	Can it be assumed that sufficient rack-mount capacity exists at each location?	No, the Rackmounts will need to be purchased for each location.
14	14)Is all trenching (including boring, underground conduit, buried cabling) and any required permits for this trenching and electrical work is to be included in our scope and price for this project.	Yes, all costs associated with providing the services described in the Scope of Work must be included in the bid, including any required permits for trenching.
15	If the 50 sites are not complete and successfully connected to Citywide ESS by September 30, 2022, will DGS call our performance bond?	Yes, it is the Department's intent to have all site completed by September 30, 2022. For the avoidance of doubt, please refer to Exhibit J.11 Rev. 5.24.2022 issued with Addendum No. 01 for the complete list of locations.
16	Do we need to provide a bid bond or a payment and performance bond? Or both?	The awarded bidder will be required to furnish a payment and performance bond.
17	Please confirm 50% SBE participation is required	All non-CBE firms are required to subcontract 50% to a DSLBD certified SBE.
18	Is the bond for the whole project (all 50 sites), or just certain facilities?	The payment and performance bond must be 35% of the total value of the contract award. Please refer to Section H.12.7 and Exhibit J.12.