SPACE	325 STUDENTS			400 STUDENTS			500 STUDENTS			700 STUDENTS		
	QTY	SF	TOTAL	QTY	SF	TOTAL	QTY	SF	TOTAL	QTY	SF	TOTAL
STUDENT DINING												
Student Dining Area	1	2,030	2,030	1	2,500	2,500	1	3,125	3,125	1	4,375	4,375
Multipurpose*	--	--	--	--	--	--	--	--	--	--	--	--
Stage**	--	--	--	--	--	--	--	--	--	--	--	--
Chair/Table Storage	1	150	150	1	175	175	1	200	200	1	275	275
Kitchen/Food Preparation***	1	650	650	1	650	650	1	650	650	1	650	650
Serving Area	1	275	275	1	275	275	1	300	300	1	400	400
Dry Food Storage	1	250	250	1	250	250	1	300	300	1	350	350
Freezer and Cooler	1	250	250	1	250	250	1	250	250	1	250	250
Ware Washing	1	100	100	1	100	100	1	150	150	1	200	200
Cleaning Storage	1	50	50	1	50	50	1	60	60	1	60	60
Food Service Office	1	150	150	1	150	150	1	150	150	1	150	150
Toilet/Lockers	1	150	150	1	150	150	1	150	150	1	150	150
TOTAL			**4,055**			**4,550**			**5,335**			**6,860**

Comments //

*This space is optional. The inclusion of this space will be determined during the site-specific Ed Spec process and approved by DCPS, based on whether or not a separate gymnasium and student dining area can be accommodated.

**Stage is listed as optional in this program and required in PE program. Final location of Stage to be determined

***Space program has been designed to accommodate a full-service kitchen. Space program should be confirmed by food service professional at time of site-specific Ed Spec development.

Note: In this document, staff assumptions were made to ensure staff spaces were approximately correct at each capacity model. Specific square footage requirements and quantity of spaces will be completed during the site specific ed spec process. Assumptions for the capacity model are: 325 students : 51 staff; 400 students : 57 staff; 500 students : 66 staff; 700 students: 81 staff.

SPACE	325 STUDENTS			400 STUDENTS			500 STUDENTS			700 STUDENTS		
	QTY	SF	TOTAL	QTY	SF	TOTAL	QTY	SF	TOTAL	QTY	SF	TOTAL
PHYSICAL EDUCATION												
Gymnasium	1	3,400	3,400	1	3,400	3,400	1	4,200	4,200	1	5,000	5,000
Stage*	1	850	850	1	850	850	1	850	850	1	850	850
Office	1	150	150	1	150	150	1	150	150	1	225	225
Storage	1	300	300	1	300	300	1	300	300	1	400	400
Chair Storage	1	100	100	1	125	125	1	150	150	1	200	200
Bicycle Storage	1	150	150	1	150	150	1	150	150	1	150	150
Outdoor PE Storage	1	100	100	1	100	100	1	100	100	1	200	200
Playgrounds	1	-	-	1	-	-	1	-	-	1	-	-
TOTAL			**5,050**			**5,075**			**5,900**			**7,025**

Comments //

Note: In this document, staff assumptions were made to ensure staff spaces were approximately correct at each capacity model. Specific square footage requirements and quantity of spaces will be completed during the site specific ed spec process. Assumptions for the capacity model are: 325 students : 51 staff; 400 students : 57 staff; 500 students : 66 staff; 700 students: 81 staff.

*Stage is listed as required in this program and optional in SD program. Final location of Stage to be determined during the site-specific Ed Spec process and approved by DCPS.